

**DATE: 18.05.2010**

**Tender No - 110290/WGI/GAIL GAS/12-R1**

<b>Sr. No.</b>	<b>Bidders Queries</b>	<b>WGI / GGL Reply to Bidders Queries</b>
1.	Please confirm the requirement is 2 system, 1 working and 1 standby system , ie working system comes with pneumatic panel , odorant storage tank and ECU , and the standby system come with 2nd nos of pneumatic panel ,and 2nd no of ECU but without the odorant storage tank. 2 SYSTEMS FOR 1 ODORIZER UNIT.	Refer data sheet of Vol-II of II, Sl.No 13 ( clearly mention that 2 system required i.e Stand by system is identical to main system except storage tank)
2.	Please confirm the electrical cabling from skid to control room is not the supplier scope. It will be scope of purchaser.	Refer Tech. Spec. of Vol-II of II, Clause no 3.8 page 6 of 10
3.	Please confirm civil design for foundation, grouting is not supplier scope. It will be scope of purchaser. Civil engineering is not included in the scope.	Refer Tech. Spec. of Vol-II of II, Clause no 6 page 8 of 10
4.	Please confirm flow computer is not supplier scope, and cabling from flow computer to odorizer panel is purchaser scope.	Refer Tech. Spec. of Vol-II of II, Clause no 3.2 page 4 of 10
5.	Please confirm cabling through underground GI pipes from control room to odorizer unit is purchaser scope . Provision of GI pipes is also not included in the vendor's supply.	Refer Tech. Spec. of Vol-II of II, Clause no 3.8 page 6 of 10
6.	Is the whole odorizer unit inclusive of the storage tank need to be cabineted or just the pneumatic panel only?	Refer Tech. Spec. of Vol-II of II, Clause no 3.5.2 & 3.8 page 5 & 6 of 10,
7.	Please confirm the customer has 2 flow meters at site and their flow computer will only give one 4 TO 20 MA signal to the ECU.	Refer Tech. Spec. of Vol-II of II, Clause no 3.2 page 4 of 10
8.	Online separate calibration device is not supplier scope.	Bidder's query is not clear.
9.	Refer to datasheet, item 13, No of injection units is it refer to 2 injectors in the pneumatic panel OR COMPLETELY 2 SYSTEM AS ABOVE QUERY NO 1.	Refer data sheet of Vol-II of II, s.n 13 ( clearly mention that 2 system required i.e Stand by system is identical to main system except storage tank)
10.	Please confirm tubing supply and installation from main pipeline to odorizer unit 's pneumatic panel is not included in the scope of supply.	Refer Tech. Spec. of Vol-II of II, Clause no 2.1 page 3 of 10